

कार्यालय जोधपुर नगर निगम-दक्षिण

क्रमांक:-न.नि.जो./दक्षिण/द्वितीय/विकास/2022-23/1471

दिनांक:- 10/2/2023

:: अल्पकालीन ई-निविदा सूचना ::

नगर निगम जोधपुर की और से निम्नलिखित कार्यो हेतु भारत सरकार एवं राज्य सरकार के विभिन्न विभागों/स्वायतशासी/निगमों/बोर्डों/राजकीय उपक्रमों में पंजीकृत ए.ए व ए. श्रेणी में पंजीकृत तथा नगर निगम जोधपुर दक्षिण में निर्धारित श्रेणी में पंजीकृत नियमानुसार योग्य संवेदको से निर्धारित प्रपत्र में मुहरबन्द ई-निविदाएं आमंत्रित की जाती है।

महत्वपूर्ण दिनांकों का विवरण

विवरण	दिनांक
ऑन लाईन निविदा फार्म जमा कराना प्रारम्भ होने की दिनांक व समय	13.2.2023 / 12.30 PM
ऑन लाईन निविदा फार्म जमा कराने की अन्तिम दिनांक व समय	20.2.2023 / 11.00 AM
ऑन लाईन निविदा खोलने की तारीख	— " — / 3.00 PM
निविदा शुल्क/धरोहर राशि की मूल प्रति अधीक्षण अभियन्ता कार्यालय में जमा कराने की दिनांक व समयावधि	— " — / 2.00 PM

निविदा का विवरण निम्न प्रकार है :-

क्र. सं.	कार्य का नाम	कार्य की अनुमानित लागत(लाखों में)	धरोहर राशि रुपये	निविदा शुल्क	कार्य पूर्ण करने की अवधि
1.	Construction of Open channel from Ishiyon ka Kabrasthan to Section -7 Railway line.	14.10	28200/-	500/-	3 माह
2.	Repairing of Interlocking work at various places During G-20.	10.00	20000/-	500/-	3 माह
3.	Repairing work in Community facility in ward no. 61 (Vidhya Park)	5.65	11300/-	500/-	3 माह
4.	Construction of BT road work at Gulab Nagar in Ward No. 35 of NNJS	33.12	66240/-	500/-	6 माह
5.	Colouring work on Divider, Railling, Bridges at various places in Nagar Nigam Jodhpur South (ARC)	20.00	40000/-	500/-	12 माह
6.	Colouring work at Traffic Gumti in Nagar Nigam Jodhpur South (ARC)	15.00	30000/-	500/-	12 माह
7.	Colouring works at various places in ward no. 32 to 47, 58 to 70 in Nagar Nigam Jodhpur South (ARC)	15.00	30000/-	500/-	12 माह
8.	Repairing and Colour wash works at various places in ward no. 01 to 05 22 to 31 in Nagar Nigam Jodhpur South (ARC)	15.00	30000/-	500/-	12 माह
9.	Colouring works at various places in ward no. 48 to 57, 71 to 80 in Nagar Nigam Jodhpur South (ARC)	15.00	30000/-	500/-	12 माह
10.	जोधपुर नगर निगम क्षेत्राधिकार में विभिन्न सार्वजनिक भवनो, पार्को, सड़क एवं चौराहो का रंग रोगन एवं चित्रकारी व माण्डने का कार्य।	20.00	40000/-	500/-	12 माह
11.	जोधपुर नगर निगम क्षेत्र के सूरसागर में वार्ड नं. 06 से 21 में सार्वजनिक भवनो, पार्को, सड़क एवं चौराहो का रंग रोगन एवं सौंदर्यकरण का कार्य।	15.00	30000/-	500/-	12 माह
12.	वार्ड नं 11 में मॉडल टॉउन में सीसी सड़क का कार्य।	8.00	16000/-	500/-	12 माह

निविदा की महत्वपूर्ण शर्तें निम्नानुसार हैं :-

1. निविदा प्रपत्रों को वेबसाईट <http://eproc.rajasthan.gov.in> से डाउनलोड किया जा सकता है। इन निविदाओं में भाग लेने वाले संवेदकों को निविदा को इलेक्ट्रॉनिक फॉरमेट में वेबसाईट <http://eproc.rajasthan.gov.in> पर जमा करानी होगी।

2. निविदा की प्रक्रिया ऑन लाईन होगी।

3. निविदा हेतु पात्र संवेदकों की श्रेणी -

किसी भी सीमा तक

रुपये 300.00 लाख तक

रुपये 150.00 लाख तक

रुपये 50.00 लाख तक

रुपये 15.00 लाख तक

- एए श्रेणी, संवेदक

- ए, श्रेणी संवेदक

- बी, श्रेणी संवेदक

- सी, श्रेणी संवेदक

- डी, श्रेणी संवेदक

4. निविदा खोलने की तिथि को किसी कारणवश यदि सम्पूर्ण निविदायें नहीं खोली जा सकती हैं, तो उसके अगले कार्य दिवस को शेष निविदायें खोलने का कार्य जारी रखा जावेगा।

ई-निविदा प्रक्रिया -

कार्य

पोटेशियल असेसमेंट

पोस्ट क्वालीफिकेशन

सड़क

150 लाख से 500 लाख तक

500 लाख से अधिक तक

अन्य निर्माण कार्य

100 लाख से 200 लाख तक

200 लाख से अधिक तक

5. निविदादाता द्वारा निविदा शुल्क, धरोहर राशि एवं प्रक्रिया शुल्क हेतु निम्नलिखित राशि कि मूल प्रति जोधपुर नगर निगम कार्यालय में नियमानुसार निविदा खोले जाने के समय से पूर्व जमा करवाना आवश्यक है। निम्नलिखित डिमांड/बैंकर चैक शुल्क ऑनलाईन निविदा फार्म जमाने की अन्तिम तिथि से पूर्व का होना आवश्यक है।

क्र. सं.	शुल्क वितरण	शुल्क	भुगतान का प्रकार	देय
1	निविदा शुल्क	उपरोक्तानुसार	डिमांड ड्राफ्ट/बैंकर चैक	आयुक्त जोधपुर नगर निगम-दक्षिण
2	धरोहर राशि	उपरोक्तानुसार	उपरोक्तानुसार	आयुक्त जोधपुर नगर निगम-दक्षिण
3	ई-टेंडरिंग प्रक्रिया शुल्क	50 लाख एवं उपर 1000/- 50 लाख से नीचे 500/-	डिमांड ड्राफ्ट/ बैंकर चैक	MD RISL, JAIPUR

6. प्रदत्त दरें निविदा खोलने की दिनांक से 90 दिवसों तक निविदा स्वीकृति हेतु मान्य (Valid) रहेगी। यदि निविदाकर्ता उस अवधि में अपनी निविदा अथवा शर्तों में किसी प्रकार का संशोधन करता है अथवा अपनी निविदा वापस ले लेता है, तो उसकी धरोहर राशि जब्त कर ली जावेगी।

7. यदि संवेदक के नजदीकी रिश्तेदार (प्रथम रक्त सम्बन्धी व उनके पति/पत्नी) कार्य से संबंधित अधीनस्थ कार्यालय में खण्डीय लेखाकार अथवा सहायक अभियन्ता से लेकर अधीक्षण अभियन्ता स्तर का किसी भी स्तर पर पदस्थापित हो, तो उसके कार्य पर नियुक्त करने पर प्रतिबन्ध रहेगा।

8. राज्य सरकार में किसी भी अभियांत्रिकी विभाग में किसी भी इंजीनियर अथवा इंजीनियर या प्रशासनिक कार्य पर नियुक्त राजपत्रित अधिकारी राज्य की अनुमति के बिना सेवा निवृत्ति के 2 वर्ष तक संवेदक अथवा उसके कर्मचारी के रूप में कार्य नहीं कर सकेंगे। यदि संवेदक अथवा उसके कर्मचारियों में कोई ऐसा व्यक्ति जिसने राज्य सरकार की उक्त लिखित अनुमति निविदा जमा कराने से पहले अथवा संवेदक के यहां से सेवायें लेने से पहले अनुमति नहीं ली है, तो अनुबन्ध रद्द किया जा सकेगा।

9. उक्त आईटम की दोष निवारण अवधि 3 वर्ष होगी।

10. निविदा में निविदादाताओं से अंतर राशि परफोरमेंस सिक्यूरिटी के रूप में प्राप्त करने के पश्चात ही स्वीकृति निविदा का कार्यादेश दिया जायेगा।
11. किसी भी निविदा को स्वीकार करने एवं बिना कारण बताये निरस्त करने के समस्त अधिकार निम्नहस्ताक्षर कर्ता को रहेगा। RPWA 100 की समस्त शर्तें उस सीमा तक मान्य/लागु होगी जिस सीमा तक के राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के विरोध में नहीं हो।
12. वित्त विभाग के आदेश संख्या एफ-1(एफ.डी./जी.एफ. एण्ड ए.आर./2007 दिनांक 30.09.11 (सर्कुलर नं. 19/2011) के अनुसार 50.00 लाख रुपये से नीचे की राशि के कार्यों के लिए 500/- व 50.00 लाख रुपये एवं अधिक राशि के कार्यों के लिए 1000/- रुपये की राशि निविदा शुल्क के अतिरिक्त देनी होगी जो डिमाण्ड ड्राफ्ट या बैंकर चैक के रूप में देय होगी। यह निविदा शुल्क के अतिरिक्त देनी होगी जो डिमाण्ड ड्राफ्ट या बैंकर चैक मैनेजिंग डायरेक्ट, आर.आई.एस.एल. के पक्ष में व जयपुर में भुगतान योग्य होना चाहिए।
13. नेगोशिएशन की आवश्यकता होने पर ई-मेल अथवा पत्र द्वारा डाक से सूचित किया जायेगा।
14. ई-टेंडरिंग के लिए निविदादाता हेतु निर्देश :-
 - इन निविदाओं में दिलचस्पी लेने वाले निविदा दाता निविदा प्रपत्रों का इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> से देख/डाउनलोड कर सकते हैं।
 - निविदाओं में भाग लेने वाले निविदादाताओं को इन्टरनेट साईट <http://www.eproc.rajasthan.gov.in> पर रजिस्टर करवाना होगा। ऑन लाईन निविदा में भाग लेने के लिए डिजिटल सर्टिफिकेट है इनफोरमेशन टेक्नोलॉजी एक्ट 2000 के तहत प्राप्त करना होगा जो इलेक्ट्रॉनिक निविदा में साईन करने हेतु काम आयेगा। निविदादाता उपरोक्त डिजिटल सर्टिफिकेट सी.सी.ए. द्वारा स्वीकृत एजेन्सी से प्राप्त कर सकते हैं। जिन निविदादाताओं के पास पूर्व में वैध डिजिटल सर्टिफिकेट है, नया डिजिटल लेने की आवश्यकता नहीं है।
 - निविदादाताओं को निविदा प्रपत्र इलेक्ट्रॉनिक फॉर्मेट में उपरोक्त वेबसाइट पर डिजिटल साईन के साथ प्रस्तुत करना होगा। जिसके प्रस्ताव अकेले भौतिक फॉर्म में स्वीकार्य नहीं होगा।
 - इलेक्ट्रॉनिक निविदा प्रपत्रों को जमा कराने से पूर्व निविदादाता यह सुनिश्चित कर लेवे की निविदा प्रपत्रों से संबंधित सभी आवश्यक दस्तावेजों की स्कैन कॉपी निविदा प्रपत्रों के साथ अटैच कर दी गयी है।
 - कोई भी टेण्डर इलेक्ट्रॉनिकली जमा कराने से किसी कारण से लेट हो जाता है तो उसका जिम्मेदार विभाग नहीं होगा।
 - टेण्डर के प्रपत्रों में आवश्यक सभी सूचियों को सम्पूर्ण रूप से भरकर ऑन लाईन दर्ज करे।
15. निविदायें राजस्थान लोक उपापन पारदर्शिता अधिनियम 2012 एवं नियम 2013 के अन्तर्गत आमंत्रित की जाती हैं। उपर अंकित समस्त प्रावधान/बंधन उस सीमा तक ही लागु होंगे जिस सीमा तक दे उस बिन्दु में उल्लेखित अधिनियम एवं नियमों के विरुद्ध नहीं हो।
16. आयुक्त नगर निगम जोधपुर के आदेश क्रमांक 9836 दिनांक 7.2.2020 एवं 9975 दिनांक 14.7.2020 अनुसार पंजीयन रिव्यू आदेश की पालना करनी होगी।
17. राजकीय अवकाश की स्थिति में आगामी कार्य दिवस की तिथि मान्य होगी।
18. श्रीमान् निदेशक, स्वायत्त शासन विभाग राजस्थान जयपुर के आदेश क्रमांक 144612-825 दिनांक 22.11.2021 की पालना में वित्त विभाग की अधिसूचना दिनांक 22.10.2021 अनुसार आर.टी.पी.पी. नियम 2013 में Additional Performance Security के लिए नियम 75-ए के अनुसार Additional Performance Security जमा करवानी होगी।

६-
आयुक्त

जोधपुर नगर निगम-दक्षिण

कार्यालय नगर निगम जोधपुर-दक्षिण

क्रमांक-न.नि.जो./दक्षिण/ द्वितीय/विकास/2022-23/1471

दिनांक-10/2/23

:- अत्यकालीन ई-निविदा सूचना :-

(यू.बी. संख्या.....)

नगर निगम जोधपुर की और से विकास कार्यो हेतु ऑनलाईन निविदा आमंत्रित की जाती है, कार्यो की विस्तृत जानकारी एवं शर्तो इत्यादि वेबसाईट <http://eproc.rajasthan.gov.in>, sppp.rajasthan.gov.in पर व जोधपुर नगर निगम की वेबसाईट urban.rajasthan.gov.in/mcjs पर देखी जा सकती है।

(सुश्री वनिता सेठ)

महापौर

नगर निगम जोधपुर-दक्षिण

(अरुण कुमार पुरोहित) I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण

क्रमांक- न.नि.जो./दक्षिण/ द्वितीय/विकास/2022-23/1472+01480

दिनांक-10/2/23

प्रतिलिपी :- सूचनार्थ एवं आवश्यक कार्यवाही हेतु।

1. श्रीमान जिला कलेक्टर महोदय, जोधपुर।
2. निदेशक/अधीक्षक अभियन्ता, स्थानीय निकाय विभाग, जयपुर।
3. अधीक्षक अभियन्ता/अधिसायी अभियन्ता, सा.नि.वि./जोधपुर विकास प्राधिकरण/नगर निगम जोधपुर।
4. वरिष्ठ लेखाधिकारी, जोधपुर नगर निगम।
5. राज्य स्तरीय प्रकाशन हेतु राजस्थान पत्रिका एवं क्षेत्रीय प्रकाशन हेतु समाचार पत्र मसू. त्रिकोण पत्रिका में वास्ते नियमानुसार प्रकाशन हेतु।
6. श्री रामेश्वर गहलोत, प्रोग्रामर नगर निगम जोधपुर दक्षिण को भेजकर लेख है कि उक्त अत्यकालीन ई-निविदा सूचना (1) urban.rajasthan.gov.in/mcjs (2) sppp.rajasthan.gov.in पर अपलोड करें एवं निविदा सूचना प्रकाशन हेतु राजस्थान संवाद जयपुर को मेल के माध्यम से भिजवायें।
7. राजस्थान संवाद जयपुर को भेजकर लेख है कि अत्यकालीन ई-निविदा सूचना एक राज्य स्तरीय समाचार पत्र एवं एक क्षेत्रीय समाचार पत्र में प्रकाशन हेतु भिजवायें।
8. संबंधित सहायक अभियन्ता श्री प्रबोध माथुर, नगर निगम(दक्षिण) को भेजकर लेख है कि संबंधित अधिसायी अभियन्ता से सम्पर्क कर उपरोक्त कार्यो की जी-सारणी एवं ई-निविदा सूचना <http://eproc.rajasthan.gov.in> पर अपलोड करें।
9. सूचना पट्ट जोधपुर नगर निगम दक्षिण/उत्तर।

(अरुण कुमार पुरोहित) I.A.S.

आयुक्त

नगर निगम जोधपुर-दक्षिण

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

o. date

ate of Sale :-

f Receipt :-

ssued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

e of work :- Colouring work at Traffic Gumti in Nagar Nigam Jodhpur South

(Rates are based on RUIDP SOR 2022)					
Sor No	Particulars	Qty	Unit	Rate	Amount
33.57.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work. For Traffic Gumti & Logo of MCJS	1	sqm	67.0	67.00
10.10	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. For Divider repair	1	mtr	312.5	312.50
30.21.4	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard jointed with neat cement slurry mixed with pigment to match the shade of tiles including rubbing and cleaning etc. complete on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Ordinary cement without any pigment	1	sqm	805	805.00
29.32	Providing & Fixing in position, MS fabrication work using angles, sqr tubes, c channels etc for various partition frame as per Design & Instructions & Complete in all aspects . Including all materials labour,finishing etc complete	1	kg	88.10	88.10
			Unit Item Rate		1272.60
			Say		15.00 Lakh

and Condition :-

कार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

टी की अवस्था में सम्बन्धित रेट मान्य होगी।

रने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा

गारण अवधि नियमानुसार रहेगी।

ह तक मान्य रहेगी

विदा स्वीकार नहीं होगी।

सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।



EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

reby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

OFFICE OF THE NAGAR NIGAM, JODHPUR

GSCHEDULE

NIT No. date
 Last Date of Sale :-
 Date of Receipt :-
 Copy issued to M/s

Sr No.
 Earnest Money : Rs.
 CR No. Dated.

Name of work- Const. of cc road in ward no. 11 near modern town

BASED ON RUIDP 2022					
S.No.	Item	N	Unit	Rate In Rs.	Amount
1	Dismantling of flexible pavements and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer.				
	Bituminous courses	15.84	cum	411.00	6510.24
	Granular courses	52.8	cum	286.00	15100.80
2	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil.	90	cum	214.50	19305.00
3	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD-20	8	each	2685.00	21480.00
4	Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	85	Cum.	2775.00	235875.00
5	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.PCC M-20	85	Cum.	5550.00	471750.00
6	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Sand, bazri,ballast, kankar upto 4 km	158.64	Cum.	178.63	28337.86
					798358.90
				SAY RS 20 LAC	

Terms and Condition :-

- सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
- कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
- जी.सारणी में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
- कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
- टंकण चुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
- कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
- दोष निवारण अवधि नियमानुसार रहेगी।
- दरें 4 माह तक मान्य रहेगी
- सशर्त निविदा स्वीकार नहीं होगी।
- निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

✓ 
 EXECUTIVE ENGINEER
 NAGAR NIGAM, JODHPUR.

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

OFFICE OF THE NAGAR NIGAM, JODHPUR
GSCHEDULE

NIT No. date

Last Date of Sale :-

Date of Receipt :-

Copy issued to M/s

Sr No.

Earnest Money : Rs.

CR No. Date

RUIDP 2022&PWD BSR 2018

Name of work- Repairing of Interlocking Work at various places in During G-20.

BASED ON RUIDP 2022

S.No.	Item	N	Unit	Rate In Rs.	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.				
	Lime Concrete, cement concrete grade M-10 (1:5:10) and below	1	cum	365.00	365.00
	Cement Concrete Grade M-15 and above and PCC blocks	1	cum	620.00	620.00
2	Earth work in excavation for roadway, including trimming bottom and side slopes in accordance with requirement of line, grades and cross sections, including disposal of surplus material with all lift and lead upto 1000 metre as per MoRT&H specification clause 301. In all type of soil.				
		1	cum	214.50	214.50
3	Supplying and stacking good earth at site of work. Note: 1) Loading, unloading and carriage to be paid extra as per actual lead. 2) Earth measured in stacks will be reduced by 20% for payment				
		1	CUM	299.50	299.50
4	Providing and fixing of precast concrete interlocking tiles of desired shape of M 30 grade manufactured from fully computerized automatic stationery hydraulic vibro pressed machine and fully computerized automatic batching plant of class A1/A2 as per BS 6717:2001. The CC interlocking paving blocks be laid on average 50mm. thick bed of coarse sand and the joint is to be filled with fine sand. Laying procedure on compacted sub-base as defined. Complete job is to be executed as per the instruction of Engineer incharge. The rates to be inclusive of all lead & Lifts etc. complete as per specifications. Tensile splitting strength, abrasion and braking load etc. as per BS 6717:2001, Grey cement.80mm thick				
		1	Sqm.	855.00	855.00
5	Supplying & fixing 560mm dia SFRC manhole frame & cover as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all respect as directed by the Engineer. HD-20				
		1	each	2685.00	2685.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).				
		1	each	4340.00	4340.00
7	Providing and laying un-reinforced, dowel jointed, plain cement concrete mix With Concrete Mixer & vibrator pavement over a prepared sub base with 43 grade cement , coarse and fine aggregate conforming to IS: 383, maximum size of coarse aggregate not exceeding 25 mm, mixed as per approved mix design, laid, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, admixtures (if required) as approved, curing compound, finishing to lines and grades complete as per drawing and as per clause 602, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.PCC M-20				
		1	Cum.	5550.00	5550.00

8	Random rubble masonry with hard stone in foundation and plinth : Cement mortar 1:6 (1 cement : 6 coarse sand)	1	cum	4245.00	4245.00
9	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 20 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand) (Inside and outside manhole)	1	Sqm.	283.50	283.50
10	Carriage of Materials by mechanical transport including loading, unloading and stacking :: Earth upto 4km	1	Cum.	223.29	223.29
11	Supplying and fixing Soorsagar Bhura or Equivalent ashlar sills, lintels and dassa, bearing, bed & top surface made perfectly even, jambs, skirting steps etc. rough dressed: upto 15 cm thick.	1	cum	4475.00	4475.00
12	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	1	mtr	312.50	312.50
13	Supply and fixing Jodhpur sand stone Machine cut Kerb stone (10cm wide 40 cm. height) fixed in white cement sand mortar 1:4 with pigment including EarthWork.	1	mtr	714.00	714.00
14	Removing & re-fixing of precast cement concrete interlocking paving blocks of all sizes over 50 mm thick course sand bedding (duly compacted) including filling of joints with sand complete in all respect.	1	Sqm.	546.00	546.00
				25728.29	
				SAY RS 10.00 LAC	

Terms and Condition :-

1. सभी प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
2. कार्य स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
3. जी.सारणी में वर्णित कार्यो के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा
4. कार्य स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
5. टंकण त्रुटी की अवस्था में सम्बंधित रेट मान्य होगी।
6. कार्य करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से
7. दोष निवारण अवधि नियमानुसार रहेगी।
8. दरें 4 माह तक मान्य रहेगी
9. सशर्त निविदा स्वीकार नहीं होगी।
10. निष्पादन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।


EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR

I/We hereby agree to do the above work @ _____ Above/below the "G" Schedule

(Signature of Contractor)

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

T No. date
 at Date of Sale :-
 e of Receipt :-
 y issued to M/s

Sr No.
 Earnest Money : Rs.
 CR No. Dated.

**me of work :- Colouring work on Divider, Railling, Bridges at various places in
 gar Nigam Jodhpur South (ARC)**

(Rates are based on RUIDP SOR 2022)						
o	Sor No	Particulars	Qty	Unit	Rate	Amount
	10.10	Providing and fixing precast cement concrete M-20 grade (Using mechanical Concrete Mixer) kerb stone top and bottom width 115 and 165 mm respectively, 250 mm high on 150 mm thick PCC M-10 grade foundation as per design, including fixing at site as per clause 408 of MoRT&H Specification including all material, labour, machinery, lighting, guarding and maintenance of diversion				
		For Divider repair	1	mtr	312.5	312.50
	21.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	1	cum	4340	4340.00
	11.64	Providing & laying interlocking terrzo cloured block plastic moulded.80 mm thickness having min. crushing strangth 40 N/mm2 laid over 40 mm thick river sand bed complete as per drawing and approved by Engineer In Charge , Complete with all respect .	1	sqm	802.0	802.00
	29.26.2	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as requiredIn gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	1	kg	117.5	117.50
	33.57.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	sqm	67.0	67.00
				Unit Item Rate		5639.0
				Say		20.00 Lakh

and Condition :

and Condition :-

कार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
 थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
 ो में वर्णित कार्यो के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
 ल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
 टी की अवस्था में सम्बन्धित रेट मान्य होगी।
 रने से पुर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने
 वारण अवधि नियमानुसार रहेगी ।
 ाह तक मान्य रहेगी
 विदा स्वीकार नहीं होगी ।
 न सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा ।



EXECUTIVE ENGINEER
 NAGAR NIGAM, JODHPUR.

reby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

NAGAR NIGAM JODHPUR SOUTH

GSCHEDULE

..... date

Sr No.

of Sale :-

Earnest Money : Rs.

Receipt :-

CR No. Dated.

ed to M/s

Work- Construction of BT road work at Gulab Nagar in Ward No. 35 of NNJS

RUIDP SOR 2022

Item	Qty.	Unit	Rate	Amount
mantling of flexible pavements and disposal of mantled materials up to a lead of 50 metres as directed Engineer. Bituminous courses	105.00	Cum	411.00	43155.00
granular courses	225.00	cum	286.50	64462.50
th work in excavation for roadway, including trimming from and side slopes in accordance with requirement of , grades and cross sections, including disposal of plus material with all lift and lead upto 1000 metre as MoRT&H specification clause 301. In all type of soil	600.00	Cum	214.50	128700.00
riage of Materials by mechanical transport including unloading and stacking : 5 km	930.00	cum	245.95	228733.50
viding, laying, spreading (with paver finisher only) and packing wet mix macadam (WMM) base course comprising of graded stone aggregate and granular material forming to RT&H specifications (Table 400-II) in layers of equal packed thickness each consolidated, including pre- wetting the material with water at OMC in mechanical roller (Pug Mill), carriage of mixed material by tippers to laying in uniform layers in base course on a well prepared sub-base/ base course and compacting with power vibratory-roller to achieve the desired density complete as per MoRT&H specification clause - 406 including all material, labour, machinery, lighting, guarding and maintenance of diversion.	450.00	sqm	1704.00	766800.00
viding and applying primer coat over prepared surface granular base with bitumen emulsion as per IS : 8887 approved quality @ 0.6 kg/sqm with the help of spray gun fitted on bitumen Container (boiler) after cleaning the surface including removing of binding material and other foreign matter with wire brushes and small picks, sweeping with brooms or soft brushes and finally dusting with old jute bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	3000.00	sqm	27.70	83100.00

[Handwritten signature]

viding and applying tack coat on the prepared surface with bitumen emulsion as per IS: 8887 and approved quantity @ 0.2 kg/sqm with the help of spray set fitted on a steam Container (boiler) after cleaning the surface with brooms or soft brushes and finally dusting with old gunny bags and compressed air to receive bituminous treatment complete as per clause 502 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	4500.00	cum	9.90	44550.00
viding and laying bituminous macadam in 50/75 mm compacted thickness on prepared surface with specified graded crushed stone aggregates as per Table 500-4, including-II for base/ binding course, loading of aggregate with F.E. loader, heating and mixing of stone aggregate and bitumen in computerised hot mix plant, transported to site by tippers to paver, laid over a previously prepared surface with paver finisher fitted with electronic sensing device to achieve required grade, level and alignment and rolling with power roller and vibratory compactor as per clauses 501.6 and 501.7 to achieve the desired compaction complete as per clause 504 of MoRT&H specification and including all material, labour, machinery, lighting, guarding and maintenance of diversion but excluding cost of primer/ tack coat. With Bitumen VG-grade 30 @ 3.3% (percentage by weight of total mix)	225.00	sqm	5380.00	1210500.00
viding and laying open graded premix carpet 20mm thick (compacted), on prepared surface in a single course wearing course, composed of specified graded crushed stone aggregate as per Table 500-23, premixed with bituminous binder @ 14.60 kg/ 10sqm (including cost of anti-stripping compound wherever required), including loading of material with F.E. loader, hot mixing of stone aggregate and bitumen in computerised hot mix plant, transporting the mixed material by tippers to paver and laying with paver finisher fitted with electronic sensor control to the required level and grade, compacting smooth with power roller 8-10 tonne capacity and finishing to required level to achieve the desired density as per clause 512 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion but excluding cost of tack coat/ seal coat. With Bitumen VG-grade 30	4500.00	sqm	106.50	479250.00
viding and applying premixed seal coat Type "B" comprising of thin application of fine aggregate 0.06 cum/ 10sqm premix with bitumen binder @ 6.8 Kg/ 10 Sqm including cost of anti-stripping compound wherever required) laying with paver finisher with electronic sensor control and rolling with power roller 8-10 tonne complete as per clause 513 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion. With Bitumen VG-grade 30	4500.00	sqm	42.50	191250.00

152

ing precast circular manhole cover and frame by taking existing precast frame and cover, providing and fixing SFRC circular spacer of required height, re-fixing manhole cover frame and cover with cement sand (1:3), including making good the damage, complete as directed by Engineer.	10.00	each	1828.00	18280.00
ing & fixing 560mm dia SFRC manhole frame & as per IS : 12592-2002 in existing manholes including grouting the frame in PCC M-15 complete in all as directed by the Engineer. HD-20	20.00	each	2685.00	53700.00
Total :				3312481.00

SAY 33.12 Lacs

Condition :-

कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
 र श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
 र्णित कार्यो के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
 कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
 अवस्था में सम्बन्धित रेट मान्य होगी।
 पुर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने
 अवधि नियमानुसार रहेगी।
 क मान्य रहेगी
 स्वीकार नहीं होगी।
 ता राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।



**EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.**

agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

..... date

e of Sale :-

Receipt :-

ued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

of work :- Colouring works at various places in ward no. 32 to 47, 58
n Nagar Nigam Jodhpur South (ARC)

(Rates are based on RUIDP SOR 2022)

No	Particulars	Qty	Unit	Rate	Amount
8.1	Colour washing such as green, blue or buff to give an even shade New work (two or more coats) with a base coat of white washing with lime	1.0	sqm	30.6	30.60
7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size).	1	cum	5260	5260.00
7.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	sqm	67.0	67.00
2.1	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	1	sqm	205.0	205.00
1	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	1	sqm	204.5	204.50
			Unit Item Rate		5767.10
			Say		15.00 Lakh

nd Condition :-

ार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

ल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

में वर्णित कार्य के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

की अवस्था में सम्बंधित रेट मान्य होगी।

ने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय

रण अवधि नियमानुसार रहेगी।

ह तक मान्य रहेगी

विदा स्वीकार नहीं होगी।

सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

reby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

OFFICE OF THE NAGAR NIGAM, JODHPUR

GSCHEDULE

No. date

Date of Sale :-

of Receipt :-

issued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

का नाम :- वार्ड सं. 61 विद्या पार्क में सार्वजनिक हॉल मरम्मत कार्य।

BASED ON RUIDP 2022 AND PWD BSR 2018					
SOR	Item	QTY	Unit	Rate In Rs.	Amount
25.8	Coursed rubble masonry (second sort) with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand)Extra for coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto two stories.				
		5.016			
		3.135			
		8.151			
		9.00	Cum	5819.00	52371.00
32.1	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)				
		46.2	Sqm		
		28.875	Sqm		
		41.25	Sqm		
		116.325	Sqm		
		120.00	Sqm	204.50	24540.00
22.1	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : 32.22.1 Flush/ Ruled pointing				
		46.2			
		28.875			
		75.075			
		80.00	Sqm	205.00	16400.00
5.88	Supply and fixing Jodhpur sand stone Machine cut Dash,Coping,sill,lintel fixed in cement sand mortar 1:4. 9 cm (3.5") thick				
		9.90			
		6.19			
		16.09	sqm	2081.00	33478.09
7.1	Finishing walls with water proofing cement paint of required shade Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litrs/10 sqm complete including cost of Priming coat				
		46.2			
		28.875			
		75.08			
		80.00	sqm	80.60	6448.00
29	Distempering with dry distemper of approved brand and manufacture (two or more coats) and of required shade on new work, over and including priming coat of whitening to give an even shade.				
		46.2	Sqm		
		28.875	Sqm		
		41.25	Sqm		

1

		116.325	Sqm		
21.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level 1:4:8 (1 Cement : 4 fine/ coarse sand : 8 graded stone aggregate 40 mm nominal size).	120.00	Sqm	95.40	11448.00
30.25.1	Kota stone slab flooring 25mm thick over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :Area of each slab 900 to 2000 sqcm	22.00	Cum	4340.00	95480.00
		151.25	mtr		
29.32	Providing & Fixing in position, MS fabrication work using angles, sqr tubes, c channels etc for various partition frame as per Design & Instructions & Complete in all aspects . including all materials labour,finishing etc complete	155.00	mtr	1299.00	201345.00
		300.00	kg	88.10	26430.00
31.5	Supply & installation of precast galvanized iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-incharge) 0.50 mm +/- 5% total coated thickness (TCT), Zinc coating 120gsm as per IS: 277 in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches while transportation and should be supplied in single length upto 12 metre or as desired by Engineer-incharge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55mm) with EPDM seal or with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead complete upto any pitch in horizontal/ vertical or curved surfaces excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	151.25			
		155.00	sqm	623.00	96565.00
50.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	10.00	sqm	97.50	975.00
				Total	565480.09

Say 5.65 Lacs

Condition :-

- गर के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
ल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
की अवस्था में सम्बंधित रेट मान्य होगी।
ने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।
रण अवधि नियमानुसार रहेगी।
तक मान्य रहेगी
दा स्वीकार नहीं होगी।
सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

by agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

IT No. date

st Date of Sale :-

te of Receipt :-

py issued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

ame of work :- Colouring works at various places in ward no. 6 to 21 in
Nagar Nigam Jodhpur South (ARC)

(Rates are based on RUIDP SOR 2022)

Sor No	Particulars	Qty	Unit	Rate	Amount
32.28.1	Colour washing such as green, blue or buff to give an even shade New work (two or more coats) with a base coat of white washing with lime	1.0	sqm	30.6	30.60
21.1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size).	1	cum	5260	5260.00
33.57.1.	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	sqm	67.0	67.00
32.22.1	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	1	sqm	205.0	205.00
32.1.1	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	1	sqm	204.5	204.50
			Unit Item Rate		5767.10
			Say		15.00 Lakh

and Condition :-

कार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

1 में वर्णित कार्य के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

ल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

री की अवस्था में सम्बंधित रेट मान्य होगी।

ने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय

रण अवधि नियमानुसार रहेगी।

ह तक मान्य रहेगी

वेदा स्वीकार नहीं होगी।

सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

SP

EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

ereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

No. date

Date of Sale :-

of Receipt :-

issued to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

ne of work :- Colouring works at various places in ward no. 48 to 57, 71
) in Nagar Nigam Jodhpur South (ARC)

(Rates are based on RUIDP SOR 2022)

or No	Particulars	Qty	Unit	Rate	Amount
28.1	Colour washing such as green, blue or buff to give an even shade New work (two or more coats) with a base coat of white washing with lime	1.0	sqm	30.6	30.60
1.7	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1:2:4 (1 Cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size).	1	cum	5260	5260.00
7.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work.	1	sqm	67.0	67.00
2.1	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : Flush/ Ruled pointing	1	sqm	205.0	205.00
1	Cement plastering including T&P, scaffolding, material and complete labpour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand)	1	sqm	204.5	204.50
			Unit Item Rate		5767.10
			Say		15.00 Lakh

Condition :-

के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

वर्णित कार्य के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

र कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

री अवस्था में सम्बन्धित रेट मान्य होगी।

से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय

अवधि नियमानुसार रहेगी।

क मान्य रहेगी

स्वीकार नहीं होगी।

रक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

by agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

NAGAR NIGAM JODHPUR (ZONE SOUTH)

RUIDP 2022&PWD BSR 2022

GSCHEDULE

..... date

f Sale :-

ceipt :-

d to M/s

Sr No.

Earnest Money : Rs.

CR No. Dated.

Work:- Repairing and Colour Wash work on various Places of Ward 1 to 5 and 22 to 31 of NNJS

Particular's	Qty.	Unit	Rate	Amount
rough rubble masonry with hard stone in foundation and plinth : Cement 1:6 (1 cement : 6 coarse sand)	1	cum	4245	4245
rough random rubble masonry with hard stone in superstructure above level and upto two stories.	1	cum	5135	5135
plastering including T&P, scaffolding, material and complete work, including cost of water, curing, racking of joints etc. with 20 mm plaster of mix : 1:4 (1 cement : 4 fine/ coarse sand) (for tank)	1	sqm	204.5	205
rough and fixing machine cut fine dressed Red/Pink sand stone or coping, with full moulding if required laid on mortar 1:4 including pointing with admixture of cement matching with the stone shade. :75 mm thick.	1	Sqm	1664	1664
rough on stone work with cement mortar 1:3 (1 cement : 3 fine sand) : and cut pointing	1	sqm	380	380
rough washing such as green, blue or buff to give an even shade : work (two or more coats) with a base coat of white washing	1	sqm	30.60	30.60
rough painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work	1	sqm	97.5	98
TOTAL				11757
SAY				15.00 LAC.

Condition :-

के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये
पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
की अवस्था में सम्बंधित रेट मान्य होगी।
से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप
ण अवधि नियमानुसार रहेगी।
तक मान्य रहेगी
दा स्वीकार नहीं होगी।



EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

reby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)

JODHPUR NAGAR NIGAM SOUTH

GSCHEDULE

NIT No. date
Last Date of Sale :-
Date of Receipt :-
Copy issued to M/s

Sr No.
Earnest Money : Rs.
CR No. Dated.

of Work :--Mandana and painting work in jodhpur nagar nigam south area at govt. building,
circle etc. (ARC)

Based on Ruidp 2022 & PWD 201

Particulars	Qty	Unit	Rate	Amount
Pointing on stone masonry in cement sand mortar 1:3 (1-Cement:3-Sand) :Flush/ Ruled pointing	1	Sqm	205	205
Cement plastering including T&P, scaffolding, material and complete labour, including cost of water, curing, racking of joints etc. with 12 mm cement plaster of mix : 32.1.1 1:4 (1 cement : 4 fine/ coarse sand)	1	Sqm	204	204
Total				409
H-Schedule				
Art painting work over walls of jodhpur city with three coat of water proof putty of approved brand after duly rubbing the surface to make the surface even and smooth. The work includes on coat of exterior primer coat of approved brand and three or more coats exterior plastic emulsion paint of approved brand over the prepared surface. Over the Rajasthani Art Painting work to be done as per direction and design pattern approved by Engineer-in-charge. The work includes the cost of all centering and shuttering scaffolding and cleaning the site properly after completion of work, the work also includes the cost of all material, man power, stencil etc. required for art painting.	1	sqm		
Art Painting different images in rajasthan pattern, building, people, animals, sculptures etc. over new/old un plastered surfaces of wall jodhpur city with two coats of exterior primer coat of approved brand and three or more coats of exterior water based plastic emulsion paint of approved brand over the prepared surface. Over this Rajasthani Art Painting work to be done as per direction and design pattern approved by Engineer-in-charge. The work includes the cost of all centering and shuttering scaffolding and cleaning the site properly after completion of work, the work also includes the cost of all material, man power, stencil etc. required	1	sqm		
Total H-Schedule				0
Total				409.00
Say				20.00 Lac

Terms and Condition :-

- प्रकार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।
- स्थल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।
- कारणी में वर्णित कार्यो के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।
- स्थल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।
- त्रुटी की अवस्था में सम्बन्धित रेट मान्य होगी।
- करने से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में निवारण अवधि नियमानुसार रहेगी।
- 4 माह तक मान्य रहेगी
- निविदा स्वीकार नहीं होगी।
- साधन सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

✓ 
EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

hereby agree to do the above work @ _____ Above/below the "G" Schedule.
Schedule

JODHPUR NAGAR NIGAM - SOUTH

GSCHEDULE

..... date
 te of Sale :-
 Receipt :-
 ued to M/s

Sr No.
 Earnest Money : Rs.
 CR No. Dated.

of Work :- Construction of Open channel from Ishiyon ka Kabristhan to Section -7 Railway

(Rates are based on RUIDP SOR 2022)

Particulars	Qty	Unit	Rate	Amount
Cleaning and removal of earth, silt, sludge, kankar, boulder, building material and garbage in existing nallah/drains including construction of bye pass arrangement to bypass water with 1.5m lift from ground level and lead upto 50 m including foul & saturated condition where pumping out or bailing out of water is required, including shoring, shuttering where required and dewatering. Making access for disposal and dressing disposal side as per the directed of the Engineer. For depth above 1.50 m and upto 3.00 m	365.63	cum	442.5	161789.06
Dismantling of existing structures like culverts, bridges, retaining walls, CC road and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 50 metres as directed by Engineer.				
Cement Concrete Grade M-15 and above and PCC blocks	58.5	cum	427	24979.5
lime Concrete, cement concrete grade M-10 (1:5:10) and below	58.5	cum	264	15444
Earth work in excavation in foundation, trenches etc. including dressing of sides and ramming of bottoms, including getting out the excavated material, refilling after laying pipe/ foundation and disposal of surplus excavated material at a lead upto 50m suitable site as per direction of Engineer for following depths, below natural ground / road top level.				
add extra for over all depth of excavation above 1.5 m and upto 3.0 over item no 4.10.1.1	195	cum	(164+11.50)	
	195	cum	175.5	34222.5
Dismantling of flexible pavements and disposal of dismantled materials up to a lead of 50 metres as directed by Engineer. Bituminous courses	11.25	Cum	411.00	4623.75
granular courses	18.75	cum	286.50	5371.88
Dismantling stone slab roofing over wooden karries or R.C.C. battens (dismantling karries and battens to be paid for separately) including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	18.75	cum	1506.00	28237.5
Providing Barricading for Trenches using 80 - 100 mm dia Wooden allies as vertical post, atleast 1.5m above ground level and atleast 30 cm below ground level at a spacing of 3 m. Two rows of PVC tape (preferably red in colour) strip barricading horizontal strip securely tied by the vertical members. Vertical members shall be painted in red and white colour. Rate is inclusive removal and cleaning of site complete in all respect	60.00	Mtr	104.50	6270.0

Handwritten signature

Providing and laying lean cement concrete 1:4:8 in Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm, aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ cum, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in concrete mixer, laid manually, compacted with surface vibrator, finishing and curing complete as per clause 601, 112 of MoRT&H specification including all material, labour, machinery, lighting, guarding and maintenance of diversion.	39	Cum		
	4.5	Cum		0
	43.50	Cum	2775	120712.5
Random rubble masonry with hard stone in foundation and plinth Cement mortar 1:6 (1 cement : 6 coarse sand)	48.75	cum		
	40.50	cum		
	89.25	cum		
	90.00	cum	4245	382050.0
Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level : 1½:3 (1 Cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	39.00	cum		
	11.25	cum		
	50.25	cum	4700	236175
Cement plastering including T&P, scaffolding, material and complete abpour, including cost of water, curing, racking of joints etc. with 15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement : 4 fine/ coarse sand) 1:6 (1 cement : 6 fine/ coarse sand)	487.50	sqm	237.00	115537.5
Carriage of Materials by mechanical transport including loading, unloading and stacking at site.				
upto 5 km	360.75	cum	165	59523.75
upto 22 km	365.63	cum	373	136378.13
Replacing sand stone slabs in roofing laid in cement mortar 1:4 (1 cement : 4 coarse sand) including necessary repairs and cement pointing with same mortar complete including disposal of rubbish to dumping ground within 50 metres of lead : Red/ white sand stone slabs 30 to 50 mm thick.	75.0	sqm	965	72375
				1403690.06
			Say	14.10 Lakh

and Condition :-

कार के कर (टैक्स) संवेदक द्वारा ही वहन किये जायेंगे।

मल पर श्रमिक व सामग्री की सुरक्षा की जिम्मेवारी संवेदक की होगी।

10 में वर्णित कार्यों के अतिरिक्त व अधिक कार्य संवेदक द्वारा दी गई दरों के आधार पर करवाये जा सकेंगे।

मल पर कार्य सम्बंधित सूचनाएं दर्शाने वाला बोर्ड संवेदक को स्वयं के स्तर पर लगाना होगा।

टी की अवस्था में सम्बंधित रेट मान्य होगी।

रस्ते से पूर्व एवं कार्य करने के पश्चात कार्य स्थल की फोटो/विडियोग्राफी सीडी आवश्यक रूप से कार्यालय में जमा कराने होंगे।

वारण अवधि नियमानुसार रहेगी।

साह तक मान्य रहेगी

निविदा स्वीकार नहीं होगी।

दैनिक सुरक्षा राशि 10 प्रतिशत मय अनुबन्ध के जमा कराना होगा।

EXECUTIVE ENGINEER
NAGAR NIGAM, JODHPUR.

hereby agree to do the above work @ _____ Above/below the "G" Schedule.

(Signature of Contractor)